
# Storm Water Permit Accountability and Process in an Urbanizing Landscape

StormCon 2015 - Austin, TX

Alan Barrows, CESSWI – Waukesha County, Wisconsin





#### **Presentation Overview**

- ✓ Brief explanation about Waukesha County regarding where its located, vital water resources, history of farming and urban development trends
- ✓ Brief explanation of our Storm Water program history and reasons for changes in permit requirements
- ✓ Strategies that we've implemented to improve compliance with permit requirements
- ✓ Methods of making storm water basin maintenance information available to owners, municipalities, inspectors and engineers

### Wisconsin

Fun Facts:

Established in 1848

72 Counties

Population is 5.8 Million

15,000 Lakes


84,000 Miles of Rivers



#### "Lake Country"

"Mukwonago River"

One of the most biologically diverse water resources in Wisconsin



#### **Sub-Continental Divide**

Runoff to the east flows to Lake Michigan

Runoff to the west flows to the Mississippi River




# Developed Lands Waukesha County 1963

#### **Legend**



Urban and residential land uses




# **Developed Lands**

Waukesha County 2010

#### <u>Legend</u>



Urban and residential land uses















### **Storm Water & Erosion Control Ordinances**

1992 – Construction Site Erosion Control

- 1998 Construction Site Erosion Control & Storm Water Management
  - Water Quality
  - Peak Flows
- 2005 Construction Site Erosion Control & Storm Water Management
  - Water Quality
  - Peak Flows
  - Volumes (infiltration/reuse)
  - Thermal Impacts

The Waukesha County Board hereby finds that storm water runoff from is polluting the water resources of the county. This ordinance is designed to address this concern by requiring all construction sites to obtain a Storm Water Permit and follow an storm water management plan. Failure to comply with this ordinance will result in bad things .....

### **Mapped Storm Water BMPs**



- ✓ Wet
- ✓ Dry
- ✓ Underground
- ✓ Above ground
- ✓ Natural
- ✓ Artificial
- ✓ Failed
- ✓ Functioning

# Constructing BMPs correctly the first time is critical to ensure proper function

- ✓ Follow approved plans & specifications
- ✓ Use proper materials
- ✓ Do inspections and provide construction oversight
- ✓ Project engineer verifies proper construction and provides asbuilt survey



When BMPs don't work as planned, people get frustrated and the storm water program loses creditability

### Who is Responsible???

- **√**Owner
- ✓ Project Engineer
- **✓** Grading Contractor
- ✓ Erosion Control Inspector
- ✓ Erosion Control Contractor
- ✓ Construction Inspector
- ✓ Regulators

YES! All of the above



I'm shovel ready!

# Pond Infall Erosion Compromises the Liner and is very difficult to repair correctly

Safety Shelf





# KENOSHA NEWS

© 2009 Kenosha News, Kenosha, Wisconsin

Site of drowning

Rehrig Pacific Co.

102nd St.

KENOSHA NEWS

95th St.

00th St.

MONDAY, SEPTEMBER 14, 2009

× ★ ★ 75¢

Watch Kenosha's only video newscast every weekday afternoon at KENOSHANEWS.COM/VIDEO\_PLAYER

### Man drowns in retention pond

# 24-year-old Kenoshan was swimming with his friends

#### KENOSHA NEWS STAFF

PLEASANT PRAIRIE — A
Kenosha man drowned Sunday afternoon while swimming in a retention pond in
a Pleasant Prairie industrial
park;

According to Pleasant Prairie Assistant Police Chief

David Mogensen, the drowning occurred in the pond near Rehrig Pacific Co., 7800 100th St., which is part of the LakeView Corporate Park.

The 24-year-old, who was not identified Sunday pending notification of family, was swimming with three friends around 1:25 p.m. when he reportedly went under the water and never resurfaced. Witnesses said the victim appeared to be struggling before he went under.

Upon arrival, members of Pleasant Prairie Fire and Rescue and the Pleasant Prairie Police Department entered the water to search for the man, but were unsuccessful. Center.

"His for under an him for Pleasant Paul Gui Guilbe

Divers from the village and surrounding departments were called and conducted an extensive search.

eventually finding the man about 2:15 p.m. in about 7 feet of water. Attempts to revive him were unsuccessful, and he was pronounced dead at St. Catherine's Medical Center

"His friends said he went under and they hadn't seen him for about 10 minutes," Pleasant Prairie Fire Chief Paul Guilbert said.

Guilbert said two divers entered the water and searched an area where other rescue personnel believed the man was. The man was found af-

ter about a half-hour search by the divers, he said.

After the man was pulled from the water, rescue workers immediately began administering CPR and did so all the way to the hospital, where he was pronounced dead, Guilbert said.

The pond, approximately two acres in size, is one of a series of stormwater retention basins in the industrial park. Neither Guilbert nor Mogensen could say Sunday

See DROWNING, Back page

# Failed Infiltration Basins Due to Construction Sedimentation

Also can be difficult to fix once they are on-line





Rule of thumb: If you have ducks or geese in your infiltration basin, its time for repair!!



# A pre-construction meeting on-site is too late for making meaningful plan changes

- ✓ Contracts have been signed
- ✓ Grading equipment has been selected and delivered to the site
- √ Seasonal issues (winter)
- ✓ Project engineer and contractor may have differing ideas about how the job will get done



### Plan Implementation Meeting ("PIM")

## Just another meeting? Not Really

- ✓ Held weeks before construction begins
- ✓ Gives the designers, regulators and contractors to discuss the approach and requirements
- ✓ Ensures that everyone has the same plan set
- Establishes expectations and timetable
- ✓ Clarifies project roles



### **Sign-off Sheet**

- ✓ I have a copy of the approved plans
- ✓ I have read the plans and understand my role in implementation
- ✓ I understand that noncompliance subjects me to enforcement action
- ✓ Approved plan date

#### Plan Implementation Sign-off Form

#### Waukesha County Storm Water Management and Erosion Control Program

Waukesha County will not issue a Storm Water Permit until proof of *Plan Implementation Sign-off* has been submitted for all applicable contractors charged with implementing the approved version of the storm water management and erosion control construction plans. This is a signed statement from each of the key people charged with implementing the storm water management and erosion control plans for a proposed project. By signing below, the following people indicate that they:

- Have a copy of the approved plans
- Have read the plans and understand their role in implementation, and
- Understands that non-compliance subjects them to enforcement action.

PLAN	DATE	

Role in Project	Printed Name	Organization or Company	Mailing Address	Signature	Phone Number	Fax	Email
Owner / Permit Applicant							
Project Engineer							
Grading Contractor							
Erosion Control Inspector							
Erosion Control Contractor							
Landscaping Contractor							
Construction Inspector							

<sup>&</sup>quot;Sign-off" of the final plans by each person noted above can be faxed to the LRD at 262-896-8298.

### **Basin Construction Inspection Schedules**

- ✓ Identifies what needs to be inspected by the project engineer or construction inspector
- ✓ Provides phone numbers and notification requirements
- ✓ Construction verification letter references the completed inspection schedule with signatures and dates
- ✓ Allows for digital photographs to be taken of basin components before they are buried or under water

Samples are available for each basin and BMP type

### Refundable Financial Assurance

- √\$20,000 per basin
- ✓ Maximum of \$60,000
- ✓ Returned to owner when:
  - ✓ As-Built survey
  - √ Verification letters
  - ✓ Maintenance agreement
  - ✓ Basin design documents
  - ✓ Pass a final inspection



### Template Verification Letters

#### Exhibit "F" Engineering/Construction Verification

DATE:	
TO:	Land Resources Division Waukesha County Department of Parks and Land Use
FROM:	Project Engineer's Name/Company
RE:	Engineering/Construction Verification for the following project:
	Project Name:
	Section, Town of
	Storm Water Permit #
	Storm Water Management Practices:
1. Any variations a the origina [Note: The	dinance.  ude one of the following two statements:]  iations from the originally approved construction plans are noted in Exhibit E. These are considered to be within the tolerances of standard construction techniques and do not affect I design as presented in Exhibit D in any way.  County may request additional documentation to support this statement depending on the evitations from the approved plans.]
Or	eviations from the approved plants f
	ign or construction changes from the originally approved construction plans are documented in and E and have been approved by Wattkesha County.
	varm season and wetland planting verification , it may be included in this exhibit.]
11-06 san	iple (Signed P.E. stamp must be included)

Planting Verification Letter (minimum requirements)

DATE:

TO: Land Resources Division

Waukesha County Department of Parks and Land Use

FROM: (Landscape Architect or other qualified professional's name and qualification)

RE: Planting Verification for the following project:

Permit #

This correspondence shall serve as verification that I have performed \_\_\_transect surveys of the designated warm season or welfand planting areas described in the approved plans for the storm water facilities for the above-referenced project and that the plantings have a minimum coverage of 70% and match at least 4 of the species descriptions on the plans. Copies of the transect survey results are attached, along with a location map and any observations of potential future maintenance concerns.



(Signed L.A. stamp must be included, if applicable)

3-25-13

### Maintenance Agreement and Addendum

- ✓ Recorded as a deed restriction
- ✓ Before construction begins:
  - ✓ Basin locations
  - ✓ Maintenance plan
- ✓ After construction is done:
  - ✓ As-built plan views and crosssections
  - ✓ Design summaries
  - √ Verification letter
  - ✓ Termination letter
    - ✓ Transfers maintenance responsibility from developer to owner



Once they go in, its only a matter of time!!



### **Storm Water Database**



**BMP List** 


- All Storm Water BMP's need to be associated with a Project.
- Each Project may have multiple BMP's associated with it.
- Listed below are all **Projects** currently entered for the community below.

Filter List

Remove Filter

		Project		ВМР		AS-Built	Date Of Last	Date Of Next
Municipality	Township	Sec. Identifier	BMP Description	Туре	Status	Date	Inspection	Inspection
Town of Summit	Summit	35 Abundant Life Church Building Expansion	NW Infiltration Basin	Infiltration Basin	In Service	1/30/2006		8/15/2009
Town of Oconomowoc	Oconomowoc	20 Alliance Bible (now Crosspoint Community) Church	Basin 1	Wet Detention Basin	In Service	6/15/2007		9/15/2009
Town of Oconomowoc	Oconomowoc	20 Alliance Bible (now Crosspoint Community) Church	Basin 2	Wet Detention Basin	In Service	6/15/2007		9/15/2009
Town of Oconomowoc	Oconomowoc	20 Alliance Bible (now Crosspoint Community) Church	Basin 3	Infiltration Basin	In Service	6/15/2007		9/15/2009
Town of Oconomowoc	Oconomowoc	20 Alliance Bible (now Crosspoint Community) Church	Vortechs Model 5000	In-ground Water Quality Device	In Service	6/15/2007		9/15/2009
Town of Eagle	Eagle	23 Amber Fields	Infiltration Basin In Outlot 2	Infiltration Basin	In Service			7/1/2009
Town of Eagle	Eagle	23 Amber Fields	Infiltration Basin In Outlot 1	Infiltration Basin	Under Construction			7/1/2008
Town of Eagle	Eagle	23 Anathoth Field	Pond 1	Dry Detention Basin	In Service			9/15/2009
Town of Eagle	Eagle	23 Anathoth Field	Pond 2	Dry Detention Basin	In Service			9/15/2009
Town of Eagle	Eagle	23 Anathoth Field	Pond 3	Dry Detention Basin	In Service			9/15/2009
Town of Eagle	Eagle	23 Anathoth Field	Pond 4	Dry Detention Basin	In Service			9/15/2009
Town of Eagle	Eagle	23 Anathoth Field	Pond 5	Dry Detention Basin	In Service			9/15/2009
Town of Oconomowoc	Oconomowoc	14 Angels Grace / ProHealthCare Hospice	Infiltration basin with wet forebay	Infiltration Basin	In Service	11/11/2004		9/1/2009
Town of Merton	Merton	34 Arrowhead High School Infiltration Basin	Arrowhead High School Infiltration Basin	Infiltration Basin	In Service			
Town of Lisbon	Lisbon	31 Arrowhead Highlands Addition #2	South Basin	Wet Detention Basin	In Service			
Town of Lisbon	Lisbon	32 Arrowhead Highlands Addition #3	Wet Detention Basin in OL #4 SE of Subdivision	Wet Detention Basin	Planned			
Town of Lisbon	Lisbon	32 Arrowhead Highlands Addition #3	Grassed Swale North of Wet Detention Basin	Grassed Swale	Planned			
Town of Lisbon	Lisbon	32 Arrowhead Meadows	Wet Detention Basin Between Lots 7&8	Wet Detention Basin	In Service	6/16/2008		9/15/2009
Town of Lisbon	Lisbon	32 Arrowhead Meadows	Grassed Swale West Side of Carlene Dr	Grassed Swale	In Service			
Town of Lisbon	Lisbon	32 Arrowhead Meadows	Grassed Swale East Side of Carlene Dr	Grassed Swale	In Service			
Town of Merton	Merton	34 Arrowhead Site Pavement Repairs 2013	Rain garden	Rain Garden	In Service			
Town of Merton	Merton	34 Arrowhead Site Pavement Repairs 2013	Infiltration trench	Infiltration Trench/Structure	In Service			
Town of Merton	Merton	34 Arrowhead Site Pavement Repairs 2013	Infiltration trench	Infiltration Trench/Structure	In Service			
Town of Merton	Merton	34 Arrowhead Site Pavement Repairs 2013	Infiltration basin	Infiltration Basin	In Service			
Town of Merton	Merton	34 Arrowhead Stadium Seating and Press Box	Infiltration trench	Infiltration Trench/Structure	In Service			
Town of Summit	Summit	15 Aurora Medical Center	Water Quality Basin 10	Wet Detention Basin	Under Construction			
Town of Summit	Summit	15 Aurora Medical Center	Water Quality Basin 20	Wet Detention Basin	Under Construction			
Town of Summit	Summit	15 Aurora Medical Center	Water Quality Basin 30	Wet Detention Basin	Under Construction			
Town of Summit	Summit	15 Aurora Medical Center	Infiltration Basin 10	Infiltration Basin	Under Construction			
Town of Summit	Summit	15 Aurora Medical Center	Infiltration Basin 20	Infiltration Basin	Under Construction			
Town of Summit	Summit	15 Aurora Medical Center	Infiltration Basin 30	Infiltration Basin	Under Construction			
Town of Lisbon	Lisbon	29 Ausblick Ski Club	NE Detention Basin	Dry Detention Basin	Planned			
Town of Lisbon	Lisbon	29 Ausblick Ski Club	NW Cooling Pond	Wet Detention Basin	Planned			
Town of Merton	Merton	26 Austin Gates	Infiltration basin	Infiltration Basin	Under Construction			/
Town of Waukesha	Waukesha	1 Auto Paint & Supply	Pond 1	Wet Detention Basin	In Service	10/23/2008		
Town of Mukwonago	Mukwonago	7 Autumn Hills South	West Basin	Infiltration Basin	In Service			
Town of Mukwonago	Mukwonago	7 Autumn Hills South	East Basin	Infiltration Basin	In Service			
Town of Oconomowoc	Oconomowoc	30 Autumn Woods Condominiums	Pond A	Wet Detention Basin	In Service	12/30/2004		9/1/2009
Town of Oconomowoc	Oconomowoc	30 Autumn Woods Condominiums	Pond B	Constructed Wetland	In Service	12/30/2004		9/1/2009
	-		- · -	<del> · · - ·</del>				1-1-1

### GIS



oom to Feature   Pan to Feature xport Feature Attachments	Create a Report   Copy	to Drawing   Add to Selected	
Details Attributes Links			
Field Name	Field Value		
BMPNumber	46		
ProjectName	Smart CSM 9892		
BMPFacilityTypeDesc	Infiltration Basin		
BMPDescription	Infiltration Basin B		
BMPDrainageArea	8.9		
BMPMaintainedBy	Lots owners		
MunicipalityDesc	Town of Genesee		
BMPQuarterSection	NW		
BMPSection	16		
BMPTownshipID	0618		
Watershed	Fox River Watershed		
SubwaterShed	Genesee Creek		
BMPCertificationPEName	Robert Kluwin, PE		
BMPCertificationCompany	Raintree Engineering, Inc.		
BMPCertificationDate	11/10/2004 12:00:00 AM		
BMPInserviceDate	11/10/2004 12:00:00 AM		
BMPStatusDesc	In Service		
LatestBMPInspectionDate			
DocumentNumbers	1000040, 3217430		
GEONorthing	363238.5		
GEOEasting	2434333.25		
BMPNextPlannedInspectionDate			

#### Storm Water BMPs on GIS

More than 650 Storm Water BMPs are on the County's GIS



Available to municipalities in the County to use for free

- ✓ BMP Type
- ✓ Description
- ✓ Drainage Area (acres)
- ✓ Maintenance Responsibility
- ✓ Engineer / Firm
- ✓ Certification Date
- ✓ Last Inspection
- ✓ Next Inspection
- ✓ Links to Images
  - ✓ Photos
  - ✓ Maintenance Agreement
  - ✓ Inspection Logs

### Storm Water Permits on GIS


Storm Water Permit Boundaries are on the County's web GIS

- ✓ Permit Status (Pending/Issued)
- ✓ Permit Holder
- ✓ Expiration Date
- ✓ Project Type
- ✓ WPDES Coverage
- ✓ Project Milestones
  - ✓ Application Date
  - ✓ Approval Date
  - ✓ Permit Issued Date
  - ✓ Compliance Issues









### Questions & Comments?

Thank you